


STATE OF KANSAS STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission, 212 No. Market Wichita, Kansas

Kingman County, Sec. 15 Twp. 30S Rge. 7W (E) (W) Location as "NE/CNW/SW" or footage from lines NW SW NE



Lease Owner Tenneco Oil Company Lease Name Kinert-Gilchrist LKC Unit Well No. 5 Office Address Suite 139, Ciudad Bldg., 3000 United Founders Blvd. Okla. City, OK, 73112 Character of Well (completed as Oil, Gas or Dry Hole) Oil Date well completed 1-28 19 56 Application for plugging filed 11-4 19 83 Application for plugging approved N.A. 19 Plugging commenced 11-19 19 83 Plugging completed 11-29 19 83 Reason for abandonment of well or producing formation Low oil production.

If a producing well is abandoned, date of last production N.A. 19 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Producing formation Lansing Kansas City Depth to top 3721 Bottom 3727 Total Depth of Well 4180 Feet Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. Row 1: Lansing Kansas City, Oil, 3721, 3727, 8-5/8", 165, None. Row 2: 5-1/2", 4179, 2929.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

- 11-19-83 MIRU Pratt Well Service. LD 62 7/8 rods & 87 3/4 rods in singles. Had trouble unseating slips in tbg head. Had to call welder & cut head. LD 8 jts. 2-7/8 upset & tbg. was 2-7/8 regular. Shut down for weekend.
11-21-83 Finish pulling tbg & run Halliburton cmt. retainer. Set @ 3500 pump 100 sx 60/40 pos. 3% gel, LD tbg. Shut down.
11-22-83 RU 5-1/2 elevator, slips, etc. Pull 20+ inches stretch, work pipe. Run in w/wireline & find top of btm cmt plug @ 3283. Shoot off 5-1/2 csg @ 2929. Recover 91 jts. Cmt top plug w/50 sx 60/40 pos 3% gel. Run plug & follow w/50 sx of cmt.
11-29-83 Top plug had dropped roughly 100 ft. Fill to surface w/cmt.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pratt Well Service Address P. O. Box 847, Pratt, Kansas, 67124

STATE OF Oklahoma, COUNTY OF Oklahoma, ss. Employee of Owner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well and that the same are true and correct. So help me God.

(Signature) Kirk S. Harbert Production Analyst Suite 139, Ciudad Bldg., 3000 United Founders Blvd., Okla. City, OK, 73112 (Address)

Subscribed and sworn to before me this 20th day of February, 1984. Karen B. Kiemler Notary Public.

My commission expires May 7, 1985

RECEIVED STATE CORPORATION COMMISSION FEB 23 1984 CONSERVATION DIVISION Wichita, Kansas 2-23-84

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Kingman NW SW NE
SEC. 15 TWP. 30S RGE. 7 XW/W
Location as in quarters or footage from lines:

Lease Owner Tenneco
Lease Name KGLKCU Well No. 5
Office Address Box 1485 Great Bend, Ks. 67530
Character of Well (Completed as Oil, Gas or Dry Hole): oil
Date Well Completed Jan. 30, 1956
Application for plugging filed October, 1983
Plugging commenced 11-19-83
Plugging completed 11-23-83
Reason for abandonment of well or producing formation Not economical to produce

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Morris Lesley

Producing formation Kansas City Depth to top _____ bottom, _____ T.D. 4180'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
		0		8 5/8		0
				5 1/2		91 jts.

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set. Perfs. at 3668-73' and 3721-27'
Pumped 50 sx. cement above and below Hallco EZSU cement retainer at
3500'. Top plugging: 100 sx. cement, 60/40 poz mix, 3% CC, 3% gel.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Pratt Well Service, Inc.

STATE OF Kansas COUNTY OF Pratt, ss.
Judy Berry (employee of owner) or (~~owner or operator~~) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.



(Signature) Judy Berry
Box 847 Pratt, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of March, 1984



Charlene M. Dudgey
Notary Public.

My Commission expires: 9/10/86

3-21-84