

KCC-KDHE

WELL PLUGGING APPLICATION

Operator: Tenneco Oil Company License# 5415

Plugging Contractor: Pratt Well Service License #

Lease Name Kinert Gilchrist LKC Unit Well# 3 API N.A.

Location SE/4 NE/4 NW/4 Sec. 15 Twp. 30S Rge. 7W County Kingman

Total Depth 4200 Plug Back Pipe Size 8-5/8 @ 269'
5-1/2 @ 4160'

Type of Well: Oil X Gas Imput Disposal D&A

Other well history:

Well Log available? Yes No X

Date you desire to plug Plugged 1-3-84

Why was well abandoned? Low Oil Production

Condition of well:

Operators suggested method of plugging well.

- ~~Bottom~~ (1) MIRU PU
- (2) POH w/tbg.
- (3) TIH w/cmt. ret., set @ 3580'
- (4) Pump 100 sx. cmt.
- (5) TOOH w/tbg.
- (6) RIH w/csg. cutter & cut @ 2750'
- (7) Pull csg. out of hole.
- ~~Top~~ (8) RU Halliburton pump 8 sx. gel.
- (9) Pump plug w/50 sx 60/40 poz, 3% gel
3% CaCl, pump 50 sx. 60/40 poz, etc.
- (10) Cut pipe 3' BGL
- (11) Weld on ID plate.

RECEIVED
STATE CORPORATION COMMISSION
APR 27 1984
4-27-84
CONSERVATION DIVISION
Wichita, Kansas

The joint office will reply to this information within 72 hours.

A field technician will work with the operator on plugging this well.

302 W. McArthur Rd.
Dodge City, Kansas 67801

Forbes Field
Topeka, Kansas 66620

202 Century Plaza Bldg.
Wichita, Kansas 67202

2501 Market Place
Salina, Kansas 67401

1 West Ash
Chanute, Kansas 66720

1014 Cody
Hays, Kansas 67601