

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-20618-00-00  
Spot: CN2N2SW Sec/Twnshp/Rge: 22-29S-7W  
2310 feet from S Section Line, 3960 feet from E Section Line  
Lease/Unit Name: VORAN E Well Number: 2  
County: KINGMAN Total Vertical Depth: 4210 feet

Operator License No.: 8061  
Op Name: OIL PRODUCERS, INC. OF KANSAS  
Address: PO BOX 8647  
WICHITA, KS 67208

Conductor Pipe: Size feet: 136.83  
Surface Casing: Size 8.625 feet: 290  
Production: Size 4.5 feet: 4210  
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 02/23/2002 2:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone:

Proposed Plugging Method: Sec actual report.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: Plugging Operations Were Not Witnessed  
Date/Time Plugging Completed: 02/23/2002 2:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The perms were covered from 4210'-4051' and capped w/4sxs of cement. The casing was recovered from 3027, and pulled to 1100', where 35sxs of cement was spotted. The casing was pulled to 750', where 35sxs of cement was spotted. The casing was pulled to 350', where cement was circulated to surface. The remaining casing was pulled and the cement was topped off.

RECEIVED  
KCC DISTRICT #2


MAR 27 2002  
3-27-02  
WICHITA, KS

Remarks: ALLIED CEMENTING 60/40 POZ. 4% GEL.

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 4-10-02

INV. NO. 2002061642