

7-29

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER: DRILLED 12/23/60

NW NW SW, SECTION 25 TOWNSHIP 29 RANGE 7W

OPERATOR LICENSE # 8740 990 FEET FROM S SECTION LINE  
OPERATOR BRAMWELL PETROLEUM INC 4950 FEET FROM E SECTION LINE  
NAME & 15183 SW 25TH AVENUE  
ADDRESS SPIVEY, KS 67142-9074  
LEASE NAME: BARNEY #3  
COUNTY: KINGMAN 135.88  
WELL TOTAL DEPTH: 4181'  
PIPE: 5 1/2" @ 4179'  
SURFACE CASING: 8 5/8" @ 279'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD  D&A

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: MIKE'S TESTING & SALVAGE

ADDRESS: CHASE, KS LICENSE: 31529

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: \_\_\_\_\_ MONTH: \_\_\_\_\_ YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: DON BRAMWELL

COMPANY NAME: BRAMWELL PETROLEUM PHONE: \_\_\_\_\_

WERE: PERFS: 4132-36'

**RECEIVED**  
KANSAS CORPORATION COMMISSION

SAND TO 4080' AND 5 SACKS

35 SACKS AT 1050'

35 SACKS AT 650'

AUG 11 1997  
8-11-97

CIRCULATE 330' TO SURFACE

CONSERVATION DIVISION  
WICHITA, KS

PLUGGING PROPOSAL RECEIVED BY: DISTRICT II


PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART (  ) NONE (  )

COMPLETED: HOUR: 12:00 DAY: 29 MONTH: 7 YEAR: 1997

ACTUAL PLUGGING REPORT: THE PERFS WERE COVERED WITH SAND TO 4080' AND CAPPED WITH 5 SACKS OF CEMENT. THE PIPE WAS RECOVERED FROM THE WELL BORE AND PULLED TO 1050' WHERE 35 SACKS OF CEMENT WAS SPOTTED. THE PIPE WAS PULLED TO 650' WHERE 35 SACKS OF CEMENT WAS SPOTTED. THE PIPE WAS PULLED TO 330' WHERE CEMENT WAS CIRCULATED TO SURFACE.

REMARKS: 60/40 POZ 4% GEL UNITED CEMENT #4160

I DID OBSERVE THIS PLUGGING.



STEVE VAN GIESON

**INVOICED**

DATE 8-13-97

INV. NO. 48782

7-29