

1-6

RECEIVED
KANSAS CORPORATION COMMISSION

2-

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

JAN 23 1994

1-2-94

CONSERVATION DIVISION
WICHITA, KS

API NUMBER: 15-095-01084-0000
NW SW SW, SECTION 34 TOWNSHIP 29 RANGE 6W

OPERATOR LICENSE # 5123 990 FEET FROM S SECTION LINE
4950 FEET FROM E SECTION LINE

OPERATOR PICKRELL DRILLING CO INC
NAME & 110 N MAIN #205
ADDRESS WICHITA KS 67202

LEASE NAME: PRUITT #2
COUNTY: KINGMAN
WELL TOTAL DEPTH: 4157' PR 3720'

135.10

PIPE: 5-1/2" @ 4148'
SURFACE CASING: 8-5/8" @ 214'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SMD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: CLARKE CORPORATION
ADDRESS: MEDICINE LODGE KS 67104 LICENSE: 5105

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1994

PLUGGING PROPOSAL RECEIVED FROM: JEFF STELLETTO
COMPANY NAME: CLARKE CORP PHONE: _____

WERE: 3592-96' (squeezed) - 3689'-3692' - CIBP 3720' - 3731'
- 3736' - SAND 3542' & 5 SX - 35 SX 1100' - 35 SX 700'
- CIRC 280'

PLUGGING PROPOSAL RECEIVED BY: _____

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART (_____) NONE (_____)

COMPLETED: HOUR: 17:30 DAY: 6 MONTH: 1 YEAR: 1994

ACTUAL PLUGGING REPORT:
PERFS SANDED BACK TO 3520' & CAPPED W/5 SX CMT -
5-1/2" WAS SHOT & RECOVERED FROM 2900' - TUB RUN BACK
IN HOLE TO 1125' & 35 SX CMT SPOTTED - TUB PULLED TO
689' & 35 SX CMT SPOTTED - TUB PULLED TO 280' & CMT
CIRC TO SURF - REMAINING TUB PULLED & TOPPED OFF

REMARKS: ALLIED #3684 COMMON CEMENT

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE 1-28-94

INV. NO. 39826

15/

STEVE VAN GIESON (AGENT)

FORM CP-2/3
REV. 3/90