

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-00118-00-00
Spot: CSESENW Sec/Twnshp/Rge: 28-29S-6W
330 feet from S Section Line, 2310 feet from W Section Line
Lease/Unit Name: VORAN Well Number: 1
County: KINGMAN Total Vertical Depth: 4543 feet

Operator License No.: 5920
Op Name: TE-PE OIL & GAS COMPANY
Address: PO BOX 522
CANTON, KS 67428

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 292 185 SX CMT
Production: Size 5.5 feet: 4548 250 SX CMT
Liner: Size feet: 5147.65

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/30/2001 3:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE TESTING & SALVAGE Phone: (620) 628-4428

Proposed Plugging Method: Perfs 3743'-45'. Sand to 3650' and 5sxs. 35sxs @ 1000', 35sxs @ 650'. Circulate cement from 342-0'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 10/30/2001 3:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The perfs were covered w/sand from 4231'-3650' and capped w/5sxs of cement. The casing was recovered from 2500' and pulled to 1000' where 35sxs of cement was spotted. The casing was pulled to 650', where 35sxs of cement was spotted. The casing was pulled to 342', where cement was circulated to surface. The remaining casing was pulled from the wellbore and the cement was topped off.

RECEIVED
KCC DISTRICT #2
NOV 29 2001 11-29-01
WICHITA, KS

Remarks: ALLIED CEMENTING 60/40 2% GEL

Plugged through: CSG

District: 02

Signed [Signature]
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 12-3-01

INV. NO. 2002061011