

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-21824-00-00  
Spot: SWNWNE Sec/Twnshp/Rge: 31-29S-6W  
1100 feet from N Section Line, 2310 feet from E Section Line  
Lease/Unit Name: SCHEER A Well Number: 1  
County: KINGMAN Total Vertical Depth: 4200 feet

Operator License No.: 6236  
Op Name: M.T.M. PETROLEUM  
Address: PO BOX 82  
SPIVEY, KS 67142

Conductor Pipe: Size feet: \$136.50  
Surface Casing: Size 8.625 feet: 221  
Production: Size feet:  
Liner: Size feet:

Well Type: OG UIC Docket No: Date/Time to Plug: 10/01/2001 8:30 AM  
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.  
Proposal Rcvd. from: JOHN ARMBRUSTER Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: Fill hole with heavy mud and spot plugs through drill pipe. 35 sxs. cement at 1,200', 35 sxs. cement at 800', 40 sxs. cement at 270', 25 sxs. cement at 60', and 15 sxs. cement in the rathole.

Plugging Proposal Received By: JACK LUTHI WitnessType: Plugging Operations Were Not Witnessed  
Date/Time Plugging Completed: 10/01/2002 10:30 AM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Filled hole with heavy mud and spotted plugs through drill pipe. Spotted 35 sxs. cement at 1,200', spotted 35 sxs. cement at 800', spotted 40 sxs. cement at 270', spotted 20 sxs. cement at 60', and filled rathole with 20 sxs. cement.

RECEIVED  
KCC DISTRICT #2

OCT 04 2002  
10-4-02  
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY ALLIED. INVOICE #9689.

Plugged through: DP

District: 02

Signed Michael Wilson  
(TECHNICIAN)

INVOICED  
DATE 10-11-02  
INV. NO. 2003066630