

2 040343  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

7-15-87 15-095-00938-0000  
API NUMBER 15-

SE, SE NE, SEC. 32, T 29 S, R 6 W/EX  
2970 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6581

Lease Name Matson Well # B-2

Operator: Bison Energy

County Kingman 121.78

Name & Address 16 W. 4th, Suite B

Well Total Depth 3747 feet

Hutchinson, KS 67501

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, KS

Company to plug at: Hour: Day: Month: Year: 19 87

Plugging proposal received from Vernon Duntz

(company name) Kelso Casing Pulling (phone)

were: 5 1/2" @3746, Perf @3700'-3704' Sand 50' above perfs. Pull pipe.

3 sxs hulls, 12 sxs gel, 115 sxs cement

Plugging Proposal Received by District #2 Office  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 13:00 Day: 15 Month: 7 Year: 19 87

ACTUAL PLUGGING REPORT Sand was dumped inside the 5 1/2" to 3650' and capped with 6 sxs

of cement. The 5 1/2" casing was shot off and recovered. The top was squeeze

plugged through the 8 5/8" by pumping 3 sxs of hulls, 12 sxs of gel and 115

sxs of 60/40 poz, 4% gel

STATE OF

7-21-87

JUL 21 1987

Remarks: Allied Cementing #2469 MX 500 SI 400# Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED  
I did not observe this plugging.

DATE 7-22-87

Signed *St. L. S.*  
(TECHNICIAN)

INV. NO. 175-87