

2 040305

API NUMBER 15- 095-21,566-0000 *R 6*

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SE NW, SEC. 2, T 29 S, R 7 WXXX

3300 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4752

Lease Name Kostner Well # A-1

Operator: Source Petroleum

County Kingman 148.69

Name & Address 910 Century Plaza Building

Well Total Depth 4575 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Phillip Hargis

Surface Casing: Size 8 5/8 feet 273

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Allen Drilling Company License Number 5418

Address Great Bend, Kansas

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Vance

(company name) Allen Drilling Company (phone) _____

were: 35 sacks at 900'

35 sacks at 293'

25 sacks at 60'

10 sacks in rathole

10 sacks in waterwell

Plugging Proposal Received by District #2 Office (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 3:15 am Day: 28 Month: 2 Year: 19 87

ACTUAL PLUGGING REPORT Drill pipe was run to 907' and the hole was circulated full of mud. Thirty five sacks of cement was then spotted in place. The pipe was pulled to 293' and another 35 sacks of cement was spotted in place. The drill pipe was pulled from hole and a solid bridge was built at 60' and then circulated with 25 sacks cement. The water well was plugged with five sacks cement. The rathole was plugged with ten sacks cement.

RECEIVED STATE CORPORATION COMMISSION

Remarks: BJ Titan 60/40 6% gel 3-1087

(If additional description is necessary, use BACK of this form.)

INVOICED (XXXXX did not observe this plugging.)

CONSERVATION DIVISION Wichita, Kansas Signed *[Signature]* (TECHNICIAN)

DATE 3-12-87

INV. NO. 16325