

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-21583-00-00  
Spot: CNWSE Sec/Twnshp/Rge: 29-29S-6W  
1980 feet from S Section Line, 1980 feet from E Section Line  
Lease/Unit Name: STUCKY-BOLDT Well Number: 1  
County: KINGMAN Total Vertical Depth: 4402 feet

Operator License No.: 6236  
Op Name: M.T.M. PETROLEUM  
Address: PO BOX 82  
SPIVEY, KS 67142

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 211  
Production: Size 4.5 feet: 4402 150 SX CMT \$ 143.07  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/27/2001 12:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (316) 727-3410

Proposed Plugging Method: Sand to 4080' and 4sxs of cement. 35sxs @ 1100'. 35sxs @ 700'. Circulate cement from 260'-0'.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: Plugging Operations Were Not Witnessed  
Date/Time Plugging Completed: 03/28/2001 6:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The well was sanded back to 4080' and capped w/4sxs of cement. The casing was recovered from 2831' and pulled to 1100', where 35sxs of cement was spotted. The casing was pulled to 700' where 35sxs of cement was spotted. The casing was pulled to 260', where cement was circulated to surface. The remaining casing was pulled and the cement was topped off.

**INVOICED**  
DATE 4-17-01  
INV. NO. 2001061675

RECEIVED  
KCC DISTRICT #2


APR 16 2001  
4-16-01  
WICHITA, KS

Remarks: UNITED CEMENTING 60/40 4% GEL

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)