

200

3-1-88

2 040404

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 19- 095-20,964-0000  
S/2 NW SW, SEC. 14, T 29 S, R 7 W/E

P

1650 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5061

Lease Name Whitelaw Well # 1

Operator: Robert F. White

County Kingman 145.89

Name & Address P O Box 20927

Well Total Depth 4489 feet

Wichita, KS 67208

Conductor Pipe: Size 4 1/2" feet 4486

Surface Casing: Size 8 5/8 feet 254

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pulling License Number 4635

Address Great Bend, KS 67530

Company to plug at: Hour: Day: Month: Year: 19

Plugging proposal received from Robert F. White

(company name) Robert F. White (phone)

were: Open hole 4486'-89' Sand to 4335 and 4 sxs. Bridge @370'-350' and fill w/redimix.

Plugging Proposal Received by District #2 Office (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 4:45pm Day: 1 Month: 3 Year: 1988

ACTUAL PLUGGING REPORT Sand was dumped down the 4 1/2" casing from 4489'-4335' and capped with 4 sxs cement through the dump bailer. The 4 1/2" casing was shot off and recovered from 3337'. The hole was bailed to 370' and a bridge was built to 350' and filled with 5 yards redimix.

RECEIVED STATE CORPORATION COMMISSION

APR 26 1988

4-26-88

Remarks: Kingman Redimix (If additional description is necessary, use BACK of this form.)

INVOICED

did not observe this plugging.

CONSERVATION DIVISION Wichita, Kansas

Signed [Signature] (TECHNICIAN)

DATE 5-5-88

INV. NO. 20542