

1080236

TO: STATE CORPORATION COMMISSION *1-06*

API NUMBER 15-067-21,110-0000  
W/2 NW NE SEC. 31, T 29 S, R 38 W

CONSERVATION DIVISION - PLUGGING SECTION 4590 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2310 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME JOHNSON WELL # 1-31

TECHNICIAN'S PLUGGING REPORT

COUNTY GRANT

OPERATOR LICENSE # 9953

WELL TOTAL DEPTH 5800 *188.50* FEET

OPERATOR: HARRIS OIL & GAS COMPANY PRODUCTION CSG: SIZE 5 1/2" @ 5793' WITH 175 SX

NAME AND 1125 17TH STREET, SUITE 2290 SURFACE CASING: SIZE 8 5/8" @ 1769' WITH 740 SX

ADDRESS DENVER, CO 80202

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD WELL  D/A

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC LICENSE NUMBER 31151

ADDRESS RT 1, BOX49BA, TYRONE, OK 73951-9731

COMPANY TO PLUG AT: HOUR: 11:00 AM DAY: 06 MONTH: 01 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM DON HORTON

(COMPANY NAME) SARGENT & HORTON PLUGGING, INC (PHONE) 580-854-6515

RECEIVED  
STATE CORPORATION COMMISSION

WERE: PERFS AT 5655-72 DV TOOL AT 2719' W/135 SX

*JAN 19 1999*  
*1-19-99*

1ST PLUG PUMPED DOWN 5 1/2" 400# HULLS AND 25 SX CEMENT, 75 BBL SPACER.

CONSERVATION DIVISION  
Wichita, Kansas

2ND PLUG PUMP 25 SX CEMENT AT 1800' IN 5 1/2" UP TO 1600'.

3RD PLUG PULLED CASING UP TO 630' PUMPED 25 SX COMMON CEMENT. TOP OF CEMENT AT APPROX.

430'. 4TH PLUG PULLED CASING UP TO 40'. PUMP 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  X PART  NONE

OPERATIONS COMPLETED: HOUR: 4:00 PM DAY: 06 MONTH: 01 YEAR: 1999

ACTUAL PLUGGING REPORT \_\_\_\_\_

1ST PLUG PUMPED DOWN 5 1/2" 400# HULLS AND 25 SX CEMENT, 75 BBL OF SPACER.

2ND PLUG PUMP 25 SX CEMENT AT 1800' IN 5 1/2" UP TO 1600'.

3RD PLUG PULLED CASING UP TO 630' PUMPED 25 SX COMMON CEMENT. TOP OF CEMENT AT APPROX.

430'. 4TH PLUG PULLED CASING UP TO 40'. PUMP 10 SX CEMENT.

REMARKS: USED COMMON CEMENT BY SARGENTS. RECOVERED 1314' OF 5 1/2" CASING.  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED *Kevin D. Shultz*  
(TECHNICIAN) FORM CP-2/3

*1-26-99*  
*60577*