

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-067-21084-00-00
Spot: NENENW Sec/Twnshp/Rge: 31-29S-38W
4950 feet from S Section Line, 2972 feet from E Section Line
Lease/Unit Name: BAILEY Well Number: 1
County: GRANT Total Vertical Depth: 5800 feet

Operator License No.: 5952
Op Name: BP AMERICA PRODUCTION COMPANY
Address: 2225 WEST OKLAHOMA AVENUE
ULYSSES, KS 67880

Conductor Pipe: Size feet: 8 1/8 8.50
Surface Casing: Size 8.625 feet: 1830 WITH 450 SX CMT
Production: Size 5.5 feet: 5800 WITH 375 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 07/10/2002 9:45 AM
Plug Co. License No.: 99997 Plug Co. Name: HALLIBURTON ENERGY SERVICES
Proposal Rcvd. from: CARY SPOHN Company: BP AMERICA Phone: (620) 356-6955

Proposed Plugging Method: PUMP 50 SX CMT WITH HULLS. FOLLOW WITH 85 BBL MUD. SET CIBP @ 1800' & 2 SX CMT. FILL WITH CMT FROM 1800' TO SURFACE. PERFORATE AT 1800'. CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 07/10/2002 2:20 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 5713'. PERFS AT 5654-60, 5666-68. DV @ 3014. TOC @ 2000' WITH 450 SX CMT. 1ST PLUG PUMPED 10 BBL WATER WITH HULLS & 50 SX CMT WITH HULLS, 500# HULLS TOTAL. DISPLACED WITH 113 BBL MUD & PRESSURED UP TO 600#. SET CIBP @ 1800', PERFORATED AT 1796'. 2ND PLUG PUMPED DOWN 10 BBL TO LOAD PRESSURED UP TO 1000# AND HELD. PERFORATED AT 1580' & PUMPED 200 SX CMT. MAXIMUM PRESSURE 1300#. SHUT IN AT 150#. PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS 8 SX CMT. MAXIMUM PRESSURE 750#. SHUT IN AT 750#.

RECEIVED
JUL 19 2002
7-19-02
KCC WICHITA

Remarks: USED 65/35 POZMIX 6% GEL 2% CC BY HALLIBURTON. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed

Kevin D Strube

(TECHNICIAN)

INVOICED JUL 16 2002

DATE

7-19-02

INV. NO.

2003060063 MP

Form CP-2/3