

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-20785-00-00
Spot: SESE Sec/Twnshp/Rge: 23-29S-9W
660 feet from S Section Line, 660 feet from E Section Line
Lease/Unit Name: MOLITOR Well Number: 2
County: KINGMAN Total Vertical Depth: 4252 feet

Operator License No.: 3067
Op Name: MOLITOR OIL, INC.
Address: 9517 SW 80TH AVE
SPIVEY, KS 67142

Conductor Pipe: Size feet: \$138.19
Surface Casing: Size 8.625 feet: 339 225 sx
Production: Size 5.5 feet: 4243 75 sx
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 04/19/2002 2:00 PM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: MARK MOLITOR Company: MOLITOR OIL CO. Phone: (620) 243-4300

Proposed Plugging Method:

Per KCC

Plugging Proposal Received By: STEVE VANGIESON
Date/Time Plugging Completed: 04/24/2002 5:00 PM

WitnessType: Plugging Operations Were Not Witnessed
KCC Agent: STEVE VANGIESON

Actual Plugging Report:

SANDED BACK OPEN HOLE TO 4200' AND CAPPED WITH 5 SKS OF CEMENT. SHOT CASING LOOSE FROM 1600' AND PULLED TO 1400', WHERE 35 SKS OF CEMENT WAS SPOTTED. PULLED CASING TO 824', AND SPOTTED 35 SKS OF CEMENT. PULLED CASING TO 344' AND CIRCULATED CEMENT TO SURFACE. PULLED REMAINING CASING AND TOPPED OFF CEMENT.

RECEIVED
KCC DISTRICT #2

SEP 25 2002


9-25-02
WICHITA, KS

Remarks: ALLIED CEMENTING 60/40 4% GEL

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 10-11-02

INV. NO. 2003060635