

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

5-22

API NUMBER: 15-095-21,525-0000  
N/2 SE, SECTION 25 TOWNSHIP 29 RANGE 9W

OPERATOR LICENSE # 5042      1980 FEET FROM S SECTION LINE  
1320 FEET FROM E SECTION LINE

OPERATOR EDMISTON OIL CO., INC.  
NAME & 125 NORTH MARKET #1260  
ADDRESS WICHITA, KS 67202

LEASE NAME: MAGILL  
COUNTY: KINGMAN

WELL TOTAL DEPTH: 4222' <sup>137.21</sup>  
PIPE: 4 1/2" @ 4222'

SURFACE CASING: 8 5/5" @ 233'

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL X INPUT WELL \_\_\_\_\_ SWD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: COMPANY EQUIPMENT  
ADDRESS: 125 NORTH MARKET #1260, WICHITA, KS 67202 LICENSE: 5042

COMPANY TO PLUG AT: HOUR: 11:00 DAY: 22 MONTH: 5 YR: 1996

PLUGGING PROPOSAL RECEIVED FROM: DALE MAY

COMPANY NAME: \_\_\_\_\_ PHONE: \_\_\_\_\_

WERE: 15 SACKS TO 2600'  
30 SACKS AT 1400'  
30 SACKS AT 950'  
280' TO 0

PLUGGING PROPOSAL RECEIVED BY: J.L.

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (X) PART {      } NONE {      }

COMPLETED: HOUR: 3:30 DAY: 22 MONTH: 5 YEAR: 1996

ACTUAL PLUGGING REPORT:  
PACKER STUCK AT 2600'. SANDED TO 2395'. PUMPED 15 SACKS ON TOP  
OF IT. PERF. 4 1/2" CASING AT 1400', 950' AND 280'. RAN TUBING  
TO 400'. PUMPED 30 SACKS. PULLED TO 950'. PUMPED 30 SACKS.  
PULLED TO 280'. CIRCULATED CEMENT TO SURFACE.

REMARKS: HALLIBURTON # 968325      60/40 POZ      4% GEL

I DID NOT OBSERVE THIS PLUGGING.

**INVOICED**

Jack Luthi  
JACK LUTHI

DATE 7-10-96

INV. NO. 45996

5-22

7-9-96  
RECEIVED  
KANSAS CORPORATION COMMISSION  
JUL 09 1996  
CONSERVATION DIVISION  
WICHITA, KS