

2 040508

8-1

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- -095-20,997-0000

SW NE NE, SEC. 26, T 29 S, R 9 W&R

4290 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Bohrer Well # A-1

Operator: TXO Prod. Corp.

County Kingman 137.89

Name & Address 1660 Lincoln Street #1800

Well Total Depth 4243 feet

Denver, CO 80264

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8-5/8 feet 246

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corp License Number 5105

Address Medicine Lodge, KS

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ Month: \_\_\_\_\_ Year: 19 \_\_\_\_\_

Plugging proposal received from Elmo Morganstien

(company name) Clarke Corp (phone) \_\_\_\_\_

were: 4-1/2" 4237' - O.H. 4237'-4243'

C.I.B.P. @ 4200' - 35 sx @ 1400' - 35 sx @ 900' - circ from 296'

RECEIVED  
STATE CORPORATION COMMISSION

10-16-89 OCT 16 1989

CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by Steve Van Gieson  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 11:30 Day: 1 Month: 8 Year: 19 89

ACTUAL PLUGGING REPORT A cast iron bridge plug was set at 4200' and capped w/4 sx

cement - casing was recovered from 2100' - tubing was run back into the hole to

1419' where a 50' cmt plug was spotted - the tubing was pulled to 908' where

another 50' cmt plug was spotted - tubing pulled to 296' and circ to surface

w/cement

Remarks: B.J. Titan 60/40 poz 2% gel  
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 10-17-89

Signed [Signature]  
(TECHNICIAN)

INV. NO. 26162