

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 2/89

**WELL PLUGGING APPLICATION FORM**  
(File One Copy)

API NUMBER 15-095-20,698-0000 (of this well).  
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR TXO Production Corp. OPERATOR'S LICENSE NO. 5171

ADDRESS 1660 Lincoln St., Ste 1800, Denver, CO 80264 PHONE # (303) 861-4246

LEASE (~~FARM~~) Miller "M" WELL NO. 1 WELL LOCATION 660' FSL & 840' FWL COUNTY Kingman

SEC. 24 TWP. 29S RGE. 9 (~~EXPT~~ (W)) TOTAL DEPTH 4255' PLUG BACK TD 4255'

**Check One:**

OIL WELL  GAS WELL  D & A  SWD or INJ WELL  DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8-5/8" SET AT 265' CEMENTED WITH 250 SACKS

CASING SIZE 4 1/2" SET AT 4247' CEMENTED WITH 150 SACKS

PERFORATED AT Open hole: 4247'-4255' Mississippian

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Fill open hole w/ sand. Dump bail 3 sxs cmt on top. Cut & pull ± 3200' 4 1/2" csg. Plug surface w/ 4 sxs hulls 25 sxs 60-40 poz-mix w/6% gel, 1 sxs hulls, 75 sxs 60-40 poz-mix w/ 6% gel. Cut off 8-5/8" csg 6' below G.L. & weld on plate.  
(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED?  - IS ACO-1 FILED?  Yes  
(If not explain.) (You should have on file)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN To be co-ordinated between KCC & TXO field personnel).

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Leamon Roberson PHONE # (316) 886-5606

ADDRESS RR #1 Box 125B Medicine Lodge, KS 67104

PLUGGING CONTRACTOR Clarke Oilfield Corporation LICENSE NO. 5171

ADDRESS 107 Fowler Medicine Lodge, KS 67104 PHONE # (316) 886-5665

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: [Signature]  
(Operator or Agent)

DATE: 7-11-90

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 16 1990  
Wichita, Kansas

6/9/91

6/9/91



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR  
KEITH R. HENLEY CHAIRMAN  
RICH KOWALEWSKI COMMISSIONER  
JACK SHRIVER COMMISSIONER  
JUDITH MCCONNELL EXECUTIVE DIRECTOR  
FRANK A. CARO, JR. GENERAL COUNSEL

CONSERVATION DIVISION  
SHARI FEIST ALBRECHT, DIRECTOR  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, KS 67202-1286  
(316) 263-3238

NOTICE OF RECEIPT OF  
WELL PLUGGING APPLICATION

July 16, 1990

TXO Production Corp.  
1660 Lincoln St., Ste. 1800  
Denver, CO 80264

Miller "M" #1  
660'FSL-840'FWL 24-29-09W  
Kingman County, KS  
API No. 15-095-20,698

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely,

*David P. Williams*

David P. Williams  
Production Supervisor

District: #2, 202 W. First St., #304  
Wichita, KS 67202