

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
RECEIVED Rev. 2/89  
STATE CORPORATION COMMISSION

MAY 25 1989

WELL PLUGGING APPLICATION FORM  
(File One Copy)

CONSERVATION DIVISION  
Wichita, Kansas

API NUMBER 15-095-20997-0000 (of this well). 6/89  
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR TXO PRODUCTION CORP OPERATOR'S LICENSE NO. 5171

ADDRESS 1660 Lincoln Street, Suite 1800 PHONE # (303) 861-4246  
SW NE NE

LEASE (~~FARM~~) Bohrer "A" WELL NO. 1 WELL LOCATION 990' ENL & 990' COUNTY Kingman

SEC. 26 TWP. 29S RGE. 9  or  (W) TOTAL DEPTH 4243' PLUG BACK TD ±4225  
4270' FSL FEL

Check One:

OIL WELL  GAS WELL  D & A  SWD or INJ WELL  DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8 5/8" SET AT 246' CEMENTED WITH 250 SACKS

CASING SIZE 4 1/2 " SET AT 4237' CEMENTED WITH 150 SACKS

PERFORATED AT Open hole completion from 4237' to 4243'.

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set CIBP @ ±4200'. Dump bail ± 4 sxs cmt on top of plug.

Pull stretch and cut 4 1/2 " csg. recover ±2700'. Plug 8 5/8" csg w/ 4 sxs hulls & 100 sxs

60-40 poz-mix w/6% gel. Cut surface casing 6' below ground level & weld plate over 8 5/8".  
(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED?  IS ACO-1 FILED? yes  
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN to be co-ordinated between KCC and TXO  
Field offices

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE  
RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Leamon Roberson PHONE # (316) 886-5606

ADDRESS P. O. Box 125B Medicine Lodge, Kansas 67104

PLUGGING CONTRACTOR Clarke Corp. LICENSE NO. 5105 6/89

ADDRESS 107 W. Fowler, P.O. Box 187, Medicine Lodge PHONE # (316) 886-5665  
Kansas 67104

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Cory West  
(Operator or Agent)  
Cory West

DATE: May 22, 1989

2

State of Kansas



Kansas Corporation Commission

MIKE HAYDEN  
KEITH H. HENLEY  
RICH KOWALEWSKI  
MARGALEE WRIGHT  
JUDITH McCONNELL  
FRANK A. CARO, JR.

GOVERNOR  
CHAIRMAN  
COMMISSIONER  
COMMISSIONER  
EXECUTIVE DIRECTOR  
GENERAL COUNSEL

THIS NOTICE  
AUG 25 1989  
EXPIRES

CONSERVATION DIVISION  
SHARI FEIST ALBRECHT, DIRECTOR  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, KS 67202-1286  
(316) 263-3238

May 25, 1989  
NOTICE OF RECEIPT OF  
WELL PLUGGING APPLICATION

TXO Production Corporation  
1660 Lincoln Street, Ste. 1800  
Denver, CO 80264

Bohrer "A" #1  
4290' FSL 990' FEL  
Sec. 26-39S-09W  
Kingman County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

*Shari Feist Albrecht*

Shari Feist Albrecht  
Director

District: #2 202 W. First, Ste. 300  
Wichita, KS 67202  
(316) 263-8809