

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 7 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Rankin of Sage Drlg. Inc. has this
date requested permission to plug the following described well:

Mr. Rankin guarantees payment of the plugging fee.

Operator's full Name: Clyde J. Cecil

Complete Address: 630 United Founders Life Tower Oklahoma City, OK

Lease Name: Allbritten Well No. 1

Location: 0 SW/SW Sec. 6 Twp. 29S Rge. 10 (E) (WW)

County: Kingman Total Depth 3775 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rankin was instructed to plug the well as follows:

249 ft 8 5/8 surface pipe cemented with 225 sacks. Fill
hole to 200 ft, plug, 1/2 sack hulls, 35 sacks cement. Mud
to 40 ft, plug, 1/2 sack hulls, 10 sacks cement to surface.
2 sacks cement in rat hole.

Very truly yours,

A. Russell Biberstein
Conservation Division Agent