

State of Kansas

FORM - CP-2



JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

SEP 30 1963

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Joe Lawnick of Tenneco Oil Co. has this date requested permission to plug the following described well:

Mr. Lawnick guarantees payment of the plugging fee.

Operator's full Name: Tenneco Oil Co.

Complete Address: 2000 Classen Bldg., Oklahoma City, Okla.

Lease Name: Byron E. Pruitt Well No. # 1

Location: NE SW Sec. 34 Twp. 29 Rge. 6 (E) (W) W

County Kingman Total Depth 4151 Oil Well

Gas Well    Input Well    SWD Well    D & A X Lost Hole   

Mr. Lawnick was instructed to plug the well as follows:

257' of 8 5/8" surface pipe, cemented with 225 sacks.  
Fill hole with drilling mud to 250', 1st cementing plug,  
1/4 sack hulls, cement with 25 sacks. Fill hole with drill-  
ing mud to 40', 2nd cementing plug, 1/4 sack hulls, cement  
with 10 sacks to base cellar. Bridge and cement rat hole  
with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent