

State of Kansas



FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 31 1963

10-31-63

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. A. B. Holladay of Mack Oil Co. has this date requested permission to plug the following described well:

Mr. Holladay guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Co.

Complete Address: 812 Union Center, Wichita, Kansas

Lease Name: Weniger Well No. # 1

Location: C NE NE Sec. 7 Twp. 29 Rge. 7 (E) (W) W

County Kingman Total Depth 4577 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Holladay was instructed to plug the well as follows:

241' of 8 5/8" surface pipe, cemented with 200 sacks.
Fill hole with drilling mud to 235', 1st cementing plug,
1/2 sack hulls, cement with 25 sacks. Fill hole with drill-
ing mud to 40', 2nd cementing plug, 1/2 sack hulls, cement
with 10 sacks to base cellar. Bridge rat & mouse hole and
cement with 4 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent