



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

RECEIVED
 NOV 26 1967
 11-20-67
 CONSERVATION DIVISION
 Wichita, Kansas

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Nov. 10, 1967.

Dear Sir:

Mr. Kenneth Smith of Flint Engine & Construction Co. has this date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.

Operator's full Name: Bachus Oil Co.

Complete Address: 721 E. Central Wichita, Kansas.

Lease Name: P. Goetz Well No. #2

Location: SE-NW-NW ^{SW} Sec. 29 Twp. 29 Rge. 9W(E)(W)W

County Kingman Total Depth 2460 Oil Well Abd.

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Smith was instructed to plug the well as follows:

- 213 ft. of 8 5/8" surface pipe circulated with cement.
- 2459 ft. of 4 1/2" pipe. Top perforation at 2220 ft. Sand to 2200 ft. & 4 sacks cement. Mud to 200 ft., 10 ft. rock bridge & 25 sacks cement. Mud to 40 ft. 10 ft. rock bridge & 10 sacks cement to surface. 1820 ft. 4 1/2" pipe pulled.

Very truly yours,

Hermon J. Austin
 Conservation Division Agent