

15-095-00567-0000

State of Kansas

FORM - CP-2



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

### State Corporation Commission

#### CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

FEB 4 1963

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Buck Hall of Knight Casing Pulling has this date requested permission to plug the following described well:

Mr. Hall guarantees payment of the plugging fee.

Operator's full Name: Morgenstern and Spector

Complete Address: P. O. Box 661, Russell, Kansas

Lease Name: Goetz Well No. # 1

Location: NE SW SW Sec. 29 Twp. 29 Rge. 9 (E) (W) W

County Kingman Total Depth 4429 Oil Well X

Gas Well    Input Well    SWD Well    D & A    Lost Hole   

Mr. Hall was instructed to plug the well as follows:

4429' of 5 1/2" long string cemented with 150 sacks, plugged back to 4413', top of perforation 4394', hole sanded to 4385'.  
360' of 8 5/8" surface pipe. Fill hole to 200' and 10' rock Bridge, cement with 20 sacks. Fill hole with mud to 40', and 10' rock bridge, cement with 10 sacks to base cellar.

Very truly yours,

Archie Elving  
 Conservation Division Agent