

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 300 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

APR 15 1963

CONSERVATION DIVISION
 WICHITA, KANSAS

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Bob Smith of Smith & Smith Casing Co. has this date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.

Operator's full Name: Texaco Oil Inc.

Complete Address: 614 Bitting Bldg., Wichita, Kansas

Lease Name: Edith Hiebsch Well No. # 1

Location: SE SW NE Sec. 29 Twp. 29 Rge. 9 (E) (W) W

County Kingman Total Depth 4471 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Smith was instructed to plug the well as follows:

354' of 10 $\frac{3}{4}$ " surface pipe cement circulated. 4462' of 7" long string, cemented with the top at 3547'. Sand hole to 4450' with 7 sacks cement. Fill hole to 200', 10' rock bridge, cement with 25 sacks. Fill hole with mud to 40', 10' rock bridge, cement with 15 sacks to base cellar.

Very truly yours,

Archie Elving
 Conservation Division Agent