

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION  
 (Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COM

FEB 8 1963

CONSERVATION DIV.  
Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Buck Hall of Knight Casing Pulling has this  
 date requested permission to plug the following described well:

Mr. Hall guarantees payment of the plugging fee.

Operator's full Name: Morgenstern and Spector Inc.

Complete Address: P. O. Box 661, Russell, Kansas

Lease Name: Hiebach Well No. # 1

Location: NE NE NW Sec. 32 Twp. 29 Rge. 9 (E) (W) W

County Kingman Total Depth 4434 Oil Well X

Gas Well    Input Well    SWD Well    D & A    Lost Hole   

Mr. Hall was instructed to plug the well as follows:

4461' of 5 1/2" long string cemented with 150 sacks. Plugged  
back to 4420'. Top of perforation 4401'. Sanded to 3990',  
387' of surface pipe 8 5/8" circulated with cement. Fill  
hole with mud to 200'. 10' rock bridge, cement with 20 sacks.  
Fill hole with mud to 40'. 10 rock bridge, cement with 10  
sacks to base cellar.

Very truly yours,

Archie Elving  
 Conservation Division Agent