

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

FEB 18 1963

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Buck Hall of Knight Casing Pulling has this date requested permission to plug the following described well:

Mr. Hall guarantees payment of the plugging fee.

Operator's full Name: Morgenstern and Spector

Complete Address: P. O. Box 661, Russell, Kansas

Lease Name: Goetz Well No. # 2

Location: NE NW NW Sec. 32 Twp. 29 Rge. 9 (E) (W) W

County Kingman Total Depth 4437 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Hall was instructed to plug the well as follows:

4437' or 5 1/2" long string cemented with 150 sacks. Plugged back to 4393'. Top of perforation 4370'. Sanded to 4360' cemented with 5 sacks. 408' of 8 5/8" surface pipe circulated with cement. Fill hole with mud to 200', 10' rock bridge, cemented with 20 sacks. Fill hole to 40' with mud, 10' rock bridge, cemented with 10 sacks to base cellar.
 Very truly yours,

Audie Elving
 Conservation Division Agent