



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED

JAN 29 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Buck Hall of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Buck Hall guarantees payment of the plugging fee.

Operator's full Name: Morgenstern And Spector

Complete Address: Box 661, Russell Kansas

Lease Name: Heibsch Well No. # 2

Location: NE SW NW Sec. 32 Twp. 29 Rge. 9 (E) (W) W

County Kingman Total Depth 4433 Oil Well         

Gas Well X Input Well          SWD Well          D & A          Lost Hole         

Mr. Hall was instructed to plug the well as follows:

398' of 8 5/8" surface pipe circulated with cement. 4433'  
of 5 1/2" long string cemented with 150 sacks. Plugged back to  
4206'. Top of perforation 4156'. Sanded to 4140' cemented  
with 5 sacks. Fill hole to 200' and 10' rock bridge with  
20 sacks cement. Fill hole with mud to 40' and 10' rock  
bridge with 10 cement to base cellar.

Very truly yours,

Audie Elving  
 Conservation Division Agent