

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

RECEIVED
 STATE CORPORATION COMMISSION

OCT 13 1964

CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Thompson of Garvey Drilling Company has this date requested permission to plug the following described well:

Mr. Thompson guarantees payment of the plugging fee.

Operator's full Name: Garvey Drilling Company

Complete Address: Route 2, Great Bend, KANSAS

Lease Name: Hartshorn Well No. #1

Location: NW-NW-SE Sec. 36 Twp. 29 Rge. 9 (E) (W) W

County Kingman Total Depth 4204 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Thompson was instructed to plug the well as follows:

252 feet of 8 5/8 inch surface pipe circulated with 150 sacks of cement.

Hole filled to 250 feet with heavy drilling mud. First cementing plug

1/4 sack Hulls and 25 sacks cement. Hole filled to 40 feet with

heavy drilling mud. Second cementing plug and 10 sacks cement to

base of cellar. Rat hole bridged with 2 sacks of cement.

Very truly yours,

R. Herman Duster
 Conservation Division Agent