

15-095-01225-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
1001 No. Broadway  
Wichita, Kansas

### WELL PLUGGING RECORD

Kingman County. Sec. 34 Twp. 29S Rge. 6W (E) (W)

Location as "NE/CNW/SW" or footage from lines NE SW  
Lease Owner Tenneco Oil Company  
Lease Name Byron E. Pruitt Well No. 1  
Office Address 2000 Classen Building, Okla. City, Okla. 73106  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 9-28 19 63  
Application for plugging filed 9-30 19 63  
Application for plugging approved September 28 19 63  
Plugging commenced September 28 19 63  
Plugging completed September 28 19 63  
Reason for abandonment of well or producing formation \_\_\_\_\_

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4151 Feet  
Show depth and thickness of all water, oil and gas formations.

#### OIL, GAS OR WATER RECORDS

#### CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
None				8 5/8"	250'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mudded to 250'. Set 25 sxs cement at 250' and 1 sxs hulls to 40', set 10 sx. cement and 1 sx hulls to surface.

**RECEIVED**  
STATE CORPORATION COMMISSION  
OCT 9 1963  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Strata Drilling, Inc.  
Address Great Bend, Kansas

STATE OF Oklahoma COUNTY OF Oklahoma  
J. H. Hudgeons (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
2000 Classen Building, Oklahoma City, Okla.  
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of October 19 63

[Signature]  
Notary Public.

My commission expires 2-1-67



DRILLERS LOG

#1 Byron Pruitt

CASING RECORD: 249.98' of new 8-5/8" surface casing.  
 COMPANY: Tenneco Oil Company  
 DESCRIPTION: NE/4 SW/4 Section 34-29S-6W Kingman County, Kansas  
 CONTRACTOR: Strata Drilling, Inc.  
 COMMENCED: September 18, 1963  
 TOTAL DEPTH: 4151'  
 COMPLETED: September 28, 1963

D. & A.

FORMATION	FROM	TO	REMARKS
Rock & Red Bed	0	42	Ran new 8-5/8" 249.98' surface casing; set and cemented at 257' with 225 sacks of 50-50 posmix, 3% HA 5. Plug down circ. cement out and jet cement away. Ran 225 sacks of regular cement, 2% gel and 3% C. C. Plug down at 6:48 A. M. September 19, 1963.
Red Bed, Shale & Shells	42	252	
Red Bed	252	260	
Shale	260	1020	
Lime & Shale	1020	1590	
Lime	1590	1750	
Shale & Lime	1750	2310	
Shale & Shells	2310	2540	
Shale & Lime	2540	3610	
Lime	3610	3788	
Shale & Lime	3788	4095	Ran two drill stem tests.
Shale, Lime & Chert	4095	4139	
Chat	4139	4151	

Total Depth 4151'

Ran electric log.

D. & A.

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 OCT 9 1963  
 CONSERVATION DIVISION  
 Wichita, Kansas

Hole plugged as follows: Plugged mud to 250'; plugged at 250' with 25 sacks of cement and 1 sack of hulls to 40'; plugged with 10 sacks of cement and 1 sack of hulls. 2 sacks of cement in mouse hole and 2 sacks in rat hole. Job completed at 5:30 A. M. September 28, 1963.

STATE OF KANSAS )  
 ) ss:  
 COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp  
 Charles W. Steincamp, President

Subscribed and sworn before me this 1st day of October, 1963.

My Commission Expires  
 December 14, 1965

Elaine H. Taylor  
 Elaine H. Taylor, Notary Public