


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

KINGMAN County, Sec. 28 Twp. 29s Rge. 6W (#) (W)
Location as "NE/CNW/SW" or footage from lines C SW SW
Lease Owner PETROLEUM, INC.
Lease Name VORAN "B" Well No. 1
Office Address ROUTE 2, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed JANUARY 17 19 61
Application for plugging filed JANUARY 17 19 61
Application for plugging approved JANUARY 17 19 61
Plugging commenced JANUARY 17 19 61
Plugging completed JANUARY 17 19 61
Reason for abandonment of well or producing formation
NO PRODUCIBLE FORMATIONS
If a producing well is abandoned, date of last production ----- 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well GILBERT TOMAN
Producing formation ----- Depth to top -0- Bottom ----- Total Depth of Well 4205 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	253'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ----- feet to ----- feet for each plug set.

MUDDED UP WITH HEAVY MUD TO 250' FOLLOWED BY A WOODEN PLUG AND 1/4 SACK OF HULLS.
PLACED 20 SACKS OF CEMENT THROUGH DRILL PIPE ON TOP OF HULLS. MUDDED UP WITH HEAVY MUD TO 35' FOLLOWED BY WOODEN PLUG AND 1/4 SACK OF HULLS. PLACED 10 SACKS OF CEMENT ON TOP OF HULLS TO BASE OF WELL CELLAR.

RECEIVED
STATE CORPORATION COMMISSION

2-3-61 FEB 3 1961

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor GARVEY DRILLING COMPANY
Address ROUTE 2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
DON SEARLE (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle
ROUTE 2, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 2ND day of FEBRUARY, 1961

APRIL 14, 1963
My commission expires
Arthur J. Miles
Notary Public.



15-095-01501-0000
WELL LOG

COMPANY PETROLEUM, INCORPORATED

SEC. 28 T. 29S R. 6W

FARM VORAN "B" NO. 1


LOC. C-SW, SW

TOTAL DEPTH 4205'

COUNTY KINGMAN CO., KANSAS

COMM. January 5, 1961 COMP. January 17, 1961

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8 5/8" @ 253' w/200 sax.

ELEVATION 1514' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

25	Sand
253	Red rock & shale
425	Red bed
1435	Shale
1749	Lime & shale
1860	Shale
2625	Shale & lime
3645	Lime & shale
3784	Lime
4015	Lime & shale
4135	Shale & lime
4140	Lime & shale
4205	Mississippi chert
4205	T. D.

RECEIVED
STATE GEOLOGICAL COMMISSION

FEB 3 1961

CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS }
County of BARTON } ss.

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 VORAN "B" well

Verne A. Morris

Subscribed and sworn to before me this 31st day of January 1961

My Commission Expires: April 14, 1963

Arthur J. Wiles
NOTARY PUBLIC