


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

KINGMAN County. Sec. 28 Twp. 29S Rge. 6 (E) (W)
Location as "NE/CNW/SW" or footage from lines. C SW NW
Lease Owner. PETROLEUM, INC.,
Lease Name. MCCORMICK "B" Well No. 1
Office Address. R.R. #2, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed 5-29- 1964
Application for plugging filed 5-29- 1964
Application for plugging approved 5-29- 1964
Plugging commenced 5-29- 1964
Plugging completed 5-29- 1964
Reason for abandonment of well or producing formation NO PRODUCIBLE FORMATIONS

If a producing well is abandoned, date of last production 19 --
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ARCHIE ELYING
Producing formation -- Depth to top -- Bottom -- Total Depth of Well 4545 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	269'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

MUDDING UP WITH HEAVY MUD TO 250', FOLLOWED BY WOODEN PLUG. PLACED 1/4
SACK HULLS ON TOP OF PLUG, FOLLOWED BY 30 SACKS CEMENT. MUDDING UP WITH
HEAVY MUD TO 40', FOLLOWED BY WOODEN PLUG, 1/4 SACK HULLS AND 15 SACKS
CEMENT TO BASE OF WELL CELLAR.

RECEIVED
STATE CORPORATION COMMISSION

6-11-64 JUN 11 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor. GARVEY DRILLING CO.
Address. R.R. #2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
MONTE CHADD (employee of owner) or (owner) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God. MONTE CHADD, DIST. PROD. SUPT.
(Signature)

R.R. #2, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 10TH day of JUNE, 1964

My commission expires SEPTEMBER 23, 1967

Notary Public.

WELL LOG

15-095-19032-0000

COMPANY Petroleum, Inc

SEC. 28 T. 29S R. 6W

FARM McCormick

NO. 1

LOC. SW NW

TOTAL DEPTH 4545'


COUNTY Kingman

COMM. 5-14-64

COMP. 5-30-64

CONTRACTOR Garvey Drilling Company

CASING 10 3/4" @ 269' w/200 sx



ELEVATION 1524 K.B.

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

30' Sand	4415' Shale
70' Clay and Red Bed	4465' Shale and Lime
165' Red Bed and Shale	4498' Lime
270' Shale and Shells	4501' Sand (Misner)
725' Red Bed and Shale	4508' Sand
1040' Shale and Shells	4532' Sand and Shale
1240' Lime and Shale	4545' Shale
1290' Shale and Shells	4545' RTD
1445' Lime and Shale	
1680' Lime	
1830' Lime and Shale	
2265' Shale and Lime	
2340' Shale and Lime Streaks	
2415' Lime	
2695' Lime and Shale	
2828' Lime and Shale Streaks	
2962' Shale and Lime	
3190' Lime and Shale	
3265' Lime	
3292' Lime and Shale	
3345' Lime (Lansing)	
3408' Lime	
3470' Lime and Shale	
3545' Lime	
3605' Lime and Shale	
3790' Lime	
3805' Lime, Base Kansas City	
3860' Shale and Lime	
3903' Lime and Shale	
3950' Lime	
4055' Lime and Shale	
4122' Shale and Lime	
4235' Mississippi Chat	
4295' Lime and Chert	
4370' Lime	
4396' Lime and Chert	

RECEIVED
STATE CORPORATION COMMISSION

JUN 11 1964

CONSERVATION DIVISION
Wichita, Kansas

State of Kansas

County of Barton

I, Sam N. Stephens of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the McCormick #1 well.

Subscribed and sworn to before me this 5th day of June 19 64

My Commission Expires: September 23rd, 1967

Charles C. Grier
NOTARY PUBLIC