

15-095-20160-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

KINGMAN County, Sec. 28 Twp. 29 Rge. (E) 6 (W)
Location as "NE/CNW/SW" or footage from lines C SE NE (150' W) of
Lease Owner SANTA-FE PIPE & SUPPLY, INC.
Lease Name PORT EARLY Well No. 3
Office Address BOX 562 - GREAT BEND, KANSAS 67530
Character of Well (completed as Oil, Gas or Dry Hole) OIL
Date well completed JUNE 1 19 69
Application for plugging filed MAY 19 19 71
Application for plugging approved MAY 20 19 71
Plugging commenced JUNE 10 19 71
Plugging completed JUNE 18 19 71
Reason for abandonment of well or producing formation DEPLETED

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well G. RUSSELL BIBERSTEIN
Producing formation Depth to top Bottom Total Depth of Well 4523' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				9 5/8"	258'	NONE
				5 1/2"	4515'	2750.62'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

4523' - 4505' - SAND
 4505' - 4465' - 5 SACKS CEMENT
 4465' - 250' - MUD
 250' - 240' - ROCK BRIDGE
 240' - BASE - DUMPED 5 YARDS READY MIX

RECEIVED
STATE CORPORATION COMMISSION
AUG 9 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor SANTA-FE PIPE & SUPPLY, INC.
Address BOX 562 - GREAT BEND, KANSAS 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
T. L. NUTT (XXXXXX) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *T. L. Nutt*

BOX 562 - GREAT BEND, KANSAS 67530 (Address)

Subscribed and sworn to before me this 4th day of August, 19 71

My commission expires July 31, 1974

Mary M. Guesnier
Mary M. Guesnier Notary Public.

9

File

DRILLERS LOG
PORT EARLY NO. 3

CASING RECORD:	OPERATOR:	Tenneco Oil Company	DESCRIPTION:
9-5/8" @ 258' w/275 sax cement	CONTRACTOR:	Sage Drilling Co.	Ap. C SE NE Sec. 28-29S-6W Kingman County, Kansas.
TOTAL DEPTH: 4523'	COMMENCED:	May 24, 1969	
	COMPLETED:	June 1, 1969	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	261	
Red Shale & Shells	261	330	
Shale & Red Bed	330	1028	
Lime & Shale	1028	1875	
Shale & Lime	1875	2725	
Lime & Shale	2725	3326	
Lime	3326	3450	
Lime & Shale	3450	4142	
Lime, Chert & Shale	4142	4349	
Shale, Lime & Chert	4349	4445	
Lime & Shale	4445	4509	
Shale, Lime & Sand	4509	4523	
			5 1/2" @ 4515' w/220 sax

RECEIVED
STATE CORPORATION COMMISSION
MAY 20 1971
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Wayne W. Kahmeyer
Wayne W. Kahmeyer



Subscribed and sworn to before me this 2nd day of June, 1969.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1970.

