

STATE OF KANSAS  
ATE CORPORATION COMMISSION  
3 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-02-3-117

15-095-00118-00-00  
API NUMBER Drilled 1960

RECEIVED

NOV 15 2001

KCC WICHITA

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE NAME Voran

WELL NUMBER 1

330 Ft. from S Section Line

2310 Ft. from <sup>W</sup>E Section Line

SEC. 28 TWP. 29S RGE. 6W (E) or (W)

COUNTY Kingman

LEASE OPERATOR Te-Pe Oil & Gas

ADDRESS P.O. Box 522 Canton, Kansas 67428

Date Well Completed \_\_\_\_\_

PHONE (620) 628-4428 OPERATORS LICENSE NO. 5920

Plugging Commenced 10-29-01

Character of Well Oil

Plugging Completed 10-31-01

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Is plugging proposal was approved on \_\_\_\_\_ (date)

By Steve VanGieson (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.O. 4543'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	292'	None
				5-1/2"	4548'	2510'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid is placed and the method or methods used in introducing it into the hole. If cement or other plugging material is used, state the character of same and depth placed, from feet to feet each side. Plugged off bottom with sand to 3650' and 5 sks. cement. Shot pipe @2510', pulled up to 1000', pumped 8 sks. gel and 35 sks. cement, pulled up to 650', pumped 2 sks. gel and 35 sks. cement, pulled up to 342' and circulated cement to surface. 60/40 pos. 4% gel.

Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Te-Pe Oil & Gas

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 12th day of November, 2001

[Signature]  
Notary Public

My Commission Expires: \_\_\_\_\_

