


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

KINGMAN County. Sec. 28 Twp. 29 Rge. (E) 6 (W)
Location as "NE/CNW/SW" or footage from lines SW SE SE (165' N. of)
Lease Owner SANTA-FE PIPE & SUPPLY, INC.
Lease Name PORT EARLY Well No. 1
Office Address BOX 562 - GREAT BEND, KANSAS 67530
Character of Well (completed as Oil, Gas or Dry Hole) OIL
Date well completed JULY 12 19 64
Application for plugging filed MAY 19 19 71
Application for plugging approved MAY 20 19 71
Plugging commenced JUNE 29 19 71
Plugging completed JULY 3 19 71
Reason for abandonment of well or producing formation DEPLETED

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well G. RUSSELL BIBERSTEIN
Producing formation Depth to top Bottom Total Depth of Well 4500' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	252'	NONE
				5 1/2"	4500'	3315.92'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

4500'	3900'	PLUG
3900'	3875'	SAND
3875'	3835'	5 SACKS CEMENT
3835'	245'	MUD
245'	235'	ROCK BRIDGE
235'	BASE	DUMPED 4 YARDS OF READY MIX

RECEIVED
STATE CORPORATION COMMISSION
AUG 9 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor SANTA-FE PIPE & SUPPLY, INC.
Address BOX 562 - GREAT BEND, KANSAS 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
T. L. NUTT (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

BOX 562 - GREAT BEND, KANSAS 67530 (Address)

SUBSCRIBED AND SWORN TO before me this 4th day of August, 19 71

My commission expires July 31, 1974

Mary M. Guesnier
Notary Public.

GABBERT-JONES INC.
WICHITA, KANSAS
DRILLERS WELL LOG

PORT EARLY #1
495' FSL AND 990' FEL
SECTION 28-29S-6W
KINGMAN COUNTY, KANSAS

COMMENCED: JULY 1, 1964
COMPLETED: JULY 12, 1964

OPERATOR TENNECO OIL COMPANY

DEPTH		FORMATION	REMARKS
FROM	To		
0	40	SAND	
40	500	RED BED & SHALE	RAN 12 JOINTS 8-5/8" CASING, SET @ 252' W/ 175 SACKS CEMENT
500	1030	SHALE & SHELLS	
1030	2500	LIME & SHALE	
2500	2550	SAND	
2550	2760	SHALE, SAND & LIME	
2760	3345	SHALE & LIME	
3345	3370	LIME	
3370	3470	LIME & SHALE	
3470	3820	LIME	
3820	4130	LIME & SHALE	
4130	4135	LIME	
4135	4140	LIME & SHALE	
4140	4166	MISSISSIPPIAN	
4166	4305	LIME & CHERT	
4305	4495	LIME	
4495	4500	SAND	
4500	TD		RAN 4500' OF 5-1/2" CASING, SET @ 4500' W/ 150 SACKS CEMENT

RECEIVED
STATE CORPORATION COMMISSION
MAY 20 1971
CONSERVATION DIVISION
Wichita, Kansas

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLER'S LOG FOR THE WELL DRILLED IN 495' FSL AND 990' FEL SECTION 28-29S-6W, KINGMAN COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall
E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 14TH DAY OF JULY, 1964, PERSONALLY APPEARED E. E. HALL TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Vira A. McKenzie
VIRA A. MCKENZIE, NOTARY PUBLIC

MY COMMISSION EXPIRES OCTOBER 2, 1967