


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Kingman County. Sec. 32 Twp. 29S Rge. 6W (E)---(W)
Location as "NE/CNW/SW" or footage from lines. NE SW NE Sec. 32-29S-6W
Lease Owner Petroleum Management, Inc.
Lease Name Matson "B" Well No. 1
Office Address Central Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 3 19 59
Application for plugging filed July 3 19 59
Application for plugging approved July 3 19 59
Plugging commenced July 3 19 59
Plugging completed July 3 19 59
Reason for abandonment of well or producing formation no oil in commercial quantities found

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hempel, Pretty Prairie, Ks.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4165' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	270'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with extra heavy rotary mud from total depth (4165') to 240'. Plug #1, 1/4 sx. Hulls and 18 sx. cement at 240', thru. d.p. Filled hole with extra heavy rotary mud from Plug #1 to 35'. Set Plug #2, 1/4 sx. Hulls and 10 sx. cement.

RECEIVED
STATE CORPORATION COMMISSION

7-10-59 JUL 10 1959

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Capitt Drilling, Inc.
Address 814 Union Center, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
L. J. Clappitt (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
814 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of July, 19 59

My commission expires September 30, 1959

[Signature]
Notary Public.

PLUGGING
FILE SEC. 32T 29 R 6W
BOOK PAGE 50 LINE 10

ROTARY DRILLING LOG

OPERATOR: Petroleum Management, Inc.
MATSON "D" #1
NE SW NE Sec. 32-29S-6W,
Kingman County, Kansas

CONTRACTOR: Capitt Drilling, Inc.
COMM: 6/15/59
COMP: 7/3/59

Remarks: Set 3-5/8" surface casing
at 270' cemented with 200
sacks MA-500 cement.

Formations:

Shale & Lime	270'
Shale, Red Bed	383'
Red Bed	570'
Shale	1000'
Shale & Shale	1415'
Shale & Lime	1585'
Lime & Shale	2005'
Shale & Lime	2365'
Lime & Shale	2840'
Lime	2905'
Lime & Shale	3567'
Lime	3607'
Lime & Shale	3622'
Lime	4085'
Lime & Shale	4135'
Lime & Chert	4165'
Rotary Total Depth (D&A)	4165'

We certify the above log is true and
correct to the best of our knowledge
and belief.

CAPITT DRILLING, INC.

L. J. Clappitt
L. J. Clappitt

RECEIVED
STATE COMMISSION

JUL 10 1959

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 32T 29 R 6W
BOOK PAGE 30 LINE 10