

15-095-21311-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Kingman SEC. 5 TWP. 29S RGE. 7 E/W
Location as in quarters or footage from lines:
C N/2 NE

Lease Owner Zorger Petroleum Co.
 Lease Name Woodson Well No. #1
 Office Address 1010 Douglas Bldg. Wichita, Kansas 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry
 Date Well Completed 12-16-82
 Application for plugging filed 12-16-82
 Plugging commenced 12-16-82
 Plugging completed 12-16-82
 Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie

Producing formation _____ Depth to top _____ bottom T.D. 4502'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	351'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

- 1st plug @ 1020', Put in 20 sx. cement thru drill pipe.
- 2nd plug @ 600', Put in 40 sx. cement thru drill pipe.
- 3rd plug @ 300', Put in 20 sx. cement thru drill pipe.
- Mud to 60', 25 sx. cement thru drill pipe.
- 10 sx. cement in rathole.
- 5 sx. cement in water well.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor White & Ellis Drilling, Inc.
401 E. Douglas, Suite 500, Wichita, Ks. 67202


STATE OF Kansas COUNTY OF Sedgwick, ss.

Ernest Sifford (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Ernest Sifford
401 E. Douglas #500 Wichita,
(Address) Ks. 67202

SUBSCRIBED AND SWORN TO before me this 27th day of December, 1982


My Commission expires:



Carolyn J. Tjaden
Carolyn J. Tjaden, Notary Public.
STATE CORPORATION COMMISSION

DEC 28 1982

CONSERVATION DIVISION
Wichita, Kansas



WHITE

AND ELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: Zorger Petroleum 1010 Douglas Bldg. 104 S. Broadway Wichita, Kansas 67202

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500,
Wichita, Ks. 67202

Lease Name Woodson Well No. #1

Sec. 5 T. 29S R. 7W Spot C N/2 NE/4

County Kingman State Kansas Elevation _____

Casing Record:

Surface: 8 5/8" @ 351' with 225 sx. 3%cc
2%gel

Production: _____ @ _____ with _____ sx.

Type Well: D & A Total Depth 4502'

Drilling Commenced 12-7-82 Drilling Completed 12-16-82

Formation	From	To	Tops
Cellar	0	7	Lansing 3350
Lime, Shale	7	3350	Kansas City 3805
Lime	3350	4090	Mississippi 4120
Sand	4090	4120	
Lime	4120	4445	
Lime, Shale	4445	4502	

RECEIVED
STATE CORPORATION COMMISSION

DEC 28 1982

CONSERVATION DIVISION
Wichita, Kansas