


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

KINGMAN County. Sec. 14 Twp. 29 Rge. 7 (E) (W)
Location as "NE/CNW/SW" or footage from lines SW NW SW
Lease Owner Mack Oil Co.
Lease Name Whitelaw Estate Well No. 1
Office Address Box 400 Duncan, Oklahoma 73533
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 12-18 19 60
Application for plugging filed 6-12 19 72
Application for plugging approved 6-13 19 72
Plugging commenced 6-15 19 72
Plugging completed 6-15 19 72
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 3-1 19 72
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. Russell Biberstein
Producing formation Viola-Miss-K.C. Depth to top _____ Bottom _____ Total Depth of Well 4545 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Lansing K.C.		3328		9 5/8"	274	None
				2 7/8"	4543	None
Mississippi		4106		2 7/8"	4533	None
				2 7/8"	3848	None
Viola		4485				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Viola Zone Mix 3 Sx gel & Hulls & 50 Sx reg. cement by Halliburton Well on vac.
Mix 25 Sx cement w/Hulls. Close in. Mix 2 Sx gel & hulls @ 600#. Mix
15 Sx & P.I. at 2300#. Well dead. Mix & P.I. 25 Sx @ 2600#. Well dead.

Mississippi Mix 1 gel & Hulls w/cement. Pumpin @ 2500#. Then pump 5 Sx in top of string thru 1" pipe.

L.K.C. Mix 3 Sx gel & Hulls & 50 Sx cement. Wait 1 hr. Mix 18 Sx cement @ 850#.

Used a total of 188 Sx reg. cement

9 Sx gel

4 Sx Hulls.

Cut off below ground level & plated top of surface.

RECEIVED
STATE CORPORATION COMMISSION
JUN 22 1972
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____

Address _____

STATE OF Oklahoma, COUNTY OF Stevens, ss.

Carl A. Bentley (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Carl A. Bentley

Box 400, Duncan, Oklahoma

(Address)

Subscribed and sworn to before me this 21st day of June, 19 72

My commission expires Sept 12, 1973

Suzanne Diesel
Notary Public.

U102A

COMPANY Socony Mobil Oil Company


SEC. 14 T. 29S R. 7W
 LOG. SW NW SW Sec. 14

FARM Whitelaw Estate NO. 1-V

TOTAL DEPTH 4545' PBD 4495'
 COMM. 9-26-60 COMP. 10-17-60

COUNTY Kingman
 KANSAS

SHOT OR TREATED Perf. 4487'-92'
 CONTRACTOR Capitt Drilling, Inc.
 ISSUED



CASING
 20 10
 15 9 - 5/8" casing @ 274' w/200 sacks cement
 12 6
 13 5
 2 - 7/8" casing @ 4543' w/170 sacks cement

ELEVATION
 GL 1582'
 PRODUCTION
 Flow 83.5 BO &
 8.4 BW/8 hrs.
 (Rate=250.5 BO &
 25 BW/24 hrs.)
 9/64" choke

Sandy Clay	20'
Sand	60'
Shale & Lime	245'
Red Rock	275'
Shale	283'
Shale & Redbed	420'
Shale & Shells	1030'
Shells & Shale	1320'
Lime w/Shale Breaks	1520'
Lime & Shale	1815'
Lime	1880'
Shale & Lime	2190'
Lime	2330'
Shale & Lime Streaks	2550'
Shale w/Lime Streaks	2795'
Lime	2927'
Shale & Lime Streaks	3175'
Shale & Lime	3250'
Sand	3306'
Lime	4010'
Lime & Shale	4107'
Chat	4123'
Lime	4418'
Shale & Lime	4545'
Total Depth	4545'

Tops:
 Heebner Shale 3096'
 Douglas Shale 3134'
 Douglas 3247'
 Lansing-KC 3328'
 Mississippi 4106'
 Viola 4485'
 Simpson 4504'

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 25 1972
 CONSERVATION DIVISION
 Wichita, Kansas

Perf. 2-7/8" casing @ 4487'-92' w/2 Jet shots/ft. 3/8" holes.