

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-189-20918-00-00

LEASE NAME TJ Isom

WELL NUMBER 3

3300 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 35 TWP. 32 RGE. 35 (E) or (W)

COUNTY Stevens

Date Well Completed _____

Plugging Commenced 9-27-02

Plugging Completed 10-02-02

RECEIVED
OCT 15 2002
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Westport Oil & Gas Company LP

ADDRESS 8908 S. Yale, Suite 340, Tulsa, OK 74137

PHONE# (918) 481-6020 OPERATORS LICENSE NO. 33002

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-27-02 (date)

by David P. Williams Jim Holland (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Chester Depth to Top 6123 Bottom 6142 T.D. 6401

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Chester</u>	<u>Oil, Gas, Water</u>	<u>6123</u>	<u>6143</u>	<u>8 5/8</u>	<u>1770</u>	<u>-0-</u>
				<u>5 1/2</u>		<u>2012</u>
				<u>2 7/8</u>	<u>6140</u>	<u>6140</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Pull rods, Circulate hole w. mud, Pull tubing, Set CIBP @6075' w/2sx cement, Cut casing @2012', Pump cement plugs as follows: 60sx 1800'-1650', 50sx-550'-450', 15sx-40' to surface, Cut off & weld steel ID plate 4' BGL.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Jerry Dunkin Well Services, Inc. License No. 8733

Address PO Box 389 Enid, OK 73702

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Westport Oil & Gas Company LP

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Terry Frohnepfel

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Terry Frohnepfel

(Address) 8908 S. Yale, Ste 340, Tulsa, OK


SUBSCRIBED AND SWORN TO before me this 10th day of Oct, 192002

Cathey Blackwell

Notary Public

My Commission Expires: 5-21-05

#01008507



Form CP-4
Revised 05-88

OR