

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-189-21092-00-00

LEASE NAME Gertrude Logan

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1

660 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 2 TWP. 32S RGE. 35 (E) or (W)

COUNTY Stevens

Date Well Completed 10-26-87

Plugging Commenced 3-7-03

Plugging Completed 3-10-03

LEASE OPERATOR Westport Oil & Gas Co.

ADDRESS 8908 S. Yale/Suite 340 Tulsa, OK 74137-3522

PHONE#(918) 481-6020 OPERATORS LICENSE NO. 31293
31269

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-07-03 (date)

by Dodge City (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Chester Depth to Top 6088 Bottom 6126 T.D. 6327

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Oil, Gas, Saltwater	6088	6126	8 5/8	1786	-0-
	Oil, Gas, Saltwater	4756	4764	5 1/2	6327	2005
	Oil, Gas, Saltwater	4806	4810			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

CIBP's were set @5930', 5160', 4700' all w/2sx cement on top of each. Tubing was ran in well and circulated w/140bbl mud, 5 1/2" casing was cut off and pulled from 2005', Tubing was ran to 1800' and cement plugs were parted as follows, 50sx 18000' 1650', 40sx 550' 450', 10sx cement 40' to surface. Surface pipe was cut off 4' BGL and steel ID plate welded in top.
(If additional description is necessary, use BACK of THIS form.)

Name of Plugging Contractor Jerry Dunkin Well Services, Inc. License No. 8733

Address PO Box 389 Enid, Oklahoma 73702

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Westport Oil & Gas Company:LP

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Terry Frohnappfel

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Terry Frohnappfel


(Address) 8908 S. Yale, Ste 340, Tulsa, OK

RECEIVED

MAR 24 2003

SUBSCRIBED AND SWORN TO before me this 21st day of March, 2003

KCC WICHITA



Cathey Blackwell

Notary Public

on Expires: 5-21-05

#01008557