

15-189-00082-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER NA
LEASE NAME Brownell #1 Unit
WELL NUMBER #1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

Center } Ft. from S Section Line
 } Ft. from E Section Line

LEASE OPERATOR Mobil

SEC. 6 TWP. 32 RGE. 35 (E) or (W)

ADDRESS P.O. Box 5444 TA Denver Co 80217

COUNTY Stevens

PHONE# (303) 298 2104 OPERATORS LICENSE NO. 5208

Date Well Completed May 1945

Character of Well Gas

Plugging Commenced 1/29/88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2/4/88

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dick Kapp - Liberal + Steve Durant - Dodge City

Is ACO-1 filed? old well NA if not, is well log attached? NA

Producing Formation Chase Depth to Top 2657 Bottom 2829 T.D. 2829

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Fluogator Chase</u>	<u>Gas</u>	<u>2829</u>	<u>2534</u>	<u>10 3/4"</u>	<u>600'</u>	<u>4'</u>
				<u>7"</u>	<u>2662'</u>	<u>4'</u>
				<u>5 1/2" (L)</u>	<u>170'</u>	<u>4'</u>
				<u>4 1/2" (L)</u>	<u>2651'</u>	<u>965'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pulled rods + tubing. Hooked up to 4 1/2" and dumped 80 Bbls 36.915 app mud followed by 50sx 50/50 Poz w/ 30% CaCl, followed by 38 bbls mud + wiper plug. Tagged wiper plug @ 2464'. Ran free point on 4 1/2" + cut 4 1/2" @ 965', pulled 30' its. Perforated 7" @ 655' w/ 2 shot s. Ran 2 7/8 to 1830' + pumped 70sx 50/50 Poz w/ 30% CaCl, displaced w/ 3 Bbls H₂O (over)
(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Patrick Well Service License No. 07547

Address P.O. Box 1273 Liberal, KS 67905

STATE OF _____ COUNTY OF _____, ss.

J.L. Douglass (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED (signature) J.L. Douglass
STATE CORPORATION COMMISSION
4-11-88 (Address) Mobil - Denver



SUBSCRIBED AND SWORN to before me this 8th day of April, 19 88

CONSERVATION DIVISION
My Commission Expires: Wichita, Kansas
Jayne Deane Notary Public

Plugging Procedure (cont)

Pulled tubing + hooked up to 7". Pumped 50 Bbls H₂O w/out establishing circulation. Pumped 100 sk down 7" @ 600-400 psig. + displaced w/ 24 Bbls of H₂O. SION. Tagged cement @ 548', CBL showed TOC @ 458'. Perforated 7" @ 425' w/ 2 shots + couldn't establish circulation. Pumped 191 sk down 7" and called it good. Cut off casing + welded plates (END)

