

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-189-21262-0000

LEASE NAME VERNON COMBES

WELL NUMBER 3

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4413.8 Ft. from S Section Line

4018.05 Ft. from E Section Line

SEC. 16 TWP. 32S RGE. 35 (E) or (W)

LEASE OPERATOR MOBIL OIL CORPORATION

COUNTY STEVENS

ADDRESS 2319 NORTH KANSAS, LIBERAL, KS 67901

Date Well Completed 10/8/88

PHONE# (316) 626-1160 OPERATORS LICENSE NO. 5208

Character of Well D&A

Plugging Commenced 11/27/90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12/3/90

The plugging proposal was approved on 11/27/90 (date)

by DUANE RANKIN, DODGE CITY DISTRICT OFFICE (KCC District Agent's Name).

Is ACO-1 filed? YES If not, Is well log attached? NA

Producing Formation CHESTER - DRY Depth to Top 5847 Bottom 6108 T.D. 6320

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From SURFACE	To 1758	Size 8-5/8"	Put in 1758	Pulled out 0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.
(SEE ATTACHED)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor HALLIBURTON License No. _____

Address P.O. BOX 1598, LIBERAL, KS 67905

RECEIVED

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: MOBIL OIL CORPORATION STATE CORPORATION COMMISSION

STATE OF KANSAS COUNTY OF SEWARD

DEC 13 1990 12-13-90

R. KELLY, ENGINEERING TECHNICIAN (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Kelly

(Address) 2319 NORTH KANSAS, LIBERAL, KS 67901



AND SWORN TO before me this 12 day of December, 19 90

Sharon A. Cook
Notary Public

My Commission Expires: 10-1-94

SUMMARY REPORT

VERNON COMBS 3
 FLUG AND ABANDONMENT
 SE NW NW 10-32-35W
 API NO 15-189-21,262

11/9/90 CALLED OUT SURVEYORS, WENT OUT AND LOCATED WELL, DUG OUT, REWELDED 8 5/8 BACK UP TO SURFACE.

11/27/90 CONTACTED KCC OUT OF DODGE CITY, KS., SPOKE TO DUANE RANKIN. SET UP A FLUGGING DATE THUR NOV. 29, 1990.

11/28/90 MOVED IN PATRICK WELL SERVICE AND RIG UP. RAN IN WITH SN, AND 55 JTS OF 2 3/8 TEG. TAG TD WITH 20' OF 56 JT., INDICATING TD AT 1700' GL. PULLED UP TO 56 JT AT 1680'+, PACKED WELL OFF AND SHUT IN OVERNIGHT.

11/29/90 HALLIBURTON ON LOCATION. TIED ONTO TEG STRING, MIX AND PUMPED IN 30 BELS OF 9#/36 VIS GEL., GOT GOOD RETURN TO SURFACE. INSPECTED CIRCULATED FLUID, FOUND TO BE GOOD 9# MUD. SHUT GEL DOWN. PULLED 30 JTS OF TEG, LEAVING 25 IN HOLE AT 764' GL. MIX AND BALANCE IN 30 SX OF 50/50 FOZ MIX, DISPLACE WITH 9# GEL. PULLED 23 JTS OF TEG., AT 60' GL., MIX AND CIRCULATED 20 SX OF 50/50 FOZ. POOH W/LAST TWO JTS., CLEANED LOCATION. RIG DOWN AND RELEASED RIG.

12/3/90 F&O CONSTRUCTION DUG OUT AROUND WELL HEAD. WILLIAMS WELDING CUT OFF AND CAP WELL. CAPED WELL 4-5' BELOW GL. BACK FILLED WELL AND PITS. CLEANED LOCATION AND MOVED OFF.

FINAL REPORT
 TOM ROMERO

CC. RAE KELLY REGULATORY
 FILE

RECEIVED
 STATE CORPORATION COMMISSION

DEC 13 1990

CONSERVATION DIVISION
 Wichita, Kansas