

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 COLORADO DERRY BUILDING  
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-189-20875-0000

LEASE NAME Vernon Corbes

WELL NUMBER 1

SPOT LOCATION SE-SE

SEC. 10 TWP. 32S RGE. 35 (E) OR (W)

COUNTY Stevens

DATE WELL COMPLETED 7-3-85

PLUGGING COMMENCED 6-27-01

PLUGGING COMPLETED 6-29-01

TYPE OR PRINT  
PLEASE FILL OUT COMPLETELY  
AND MAKE REQUIRED AFFIDAVIT.

LEASE OPERATOR Belco Energy Corporation

ADDRESS 8908 S. Yale Suite 340 Tuls, OK 74137-3522

PHONE # (618) 481-6020

OPERATORS LICENSE NO. 31269

CHARACTER OF WELL Oil  
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? YES

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Dodge City

IS ACO-1 FILED? Yes IF NOT, IS WELL LOG ATTACHED? Yes

PRODUCING FORMATION CHESTER DEPTH TO TOP \_\_\_\_\_ BOTTOM \_\_\_\_\_ T.D. 6400

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION      | CONTENT              | FROM        | TO          | SIZE         | PUT IN      | PULLED OUT  |
|----------------|----------------------|-------------|-------------|--------------|-------------|-------------|
| <u>CHESTER</u> | <u>Oil &amp; Gas</u> | <u>6074</u> | <u>6099</u> | <u>9 5/8</u> | <u>1759</u> | <u>-0-</u>  |
|                |                      |             |             | <u>5 1/2</u> | <u>6400</u> | <u>1850</u> |
|                |                      |             |             |              |             |             |
|                |                      |             |             |              |             |             |

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET.

Circulated hole w/mud, Set CIBP @6020' w/2sx cement, Cut off casing @1850', Pumped 65sx cement +770' to 1600', Pumped 50sx cement 550' to 450', Circulated 15sx cement from 40' to surface, Cut off & welded steel TD plate 4' BG.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Jerry Dunkin Well Services, Inc.

LICENSE NO. 8733


ADDRESS PO Box 389 Enid, OK 73702

STATE OF \_\_\_\_\_ COUNTY OF \_\_\_\_\_, SS.

PAUL DAVIS

(EMPLOYEE OF OPERATOR) OR

(OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.



(SIGNATURE)

Paul Davis

(ADDRESS)

8908 S YALE  
TULSA OK 74137

SUBSCRIBED AND SWORN TO BEFORE ME THIS 16 DAY OF August, 2001

Terry Frohnappel

NOTARY PUBLIC

MY COMMISSION EXPIRES: 1-23-01

RECEIVED  
ST. CORPORATION COMMISSION

AUG 20 2001

FORM CP-4  
REVISED 06-83

Conservation Division  
Wichita, Kansas

OR