

15-189-00009-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Finney State Office Building  
130 South Market, Rm 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

RECEIVED  
KANSAS CORPORATION  
TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days  
1997 SEP 25  
9-25-97

API NUMBER NA (SPUD 01/16/59)

LEASE NAME HOWELL RHINEHART

WELL NUMBER #2-23

1738' Ft. from S Section Line

963' Ft. from W Section Line

SEC. 23 TWP. 32S RGE 39 (E) or (W)

COUNTY STEVENS

Date Well Completed 03/09/59

Plugging Commenced 08/19/97

Plugging Completed 08/22/97

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 08/08/97 (date)

by MR. GARY WINTERS (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached?

Producing Formation PANOMA COUNCIL GROVE Depth to Top 2692' Bottom 2856' T.D. 6200'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
PANOMA COUNCIL GROVE	GAS	2692'	2856'	13-3/8"	458	4'
				8-5/8"	2612	630'
				4-1/2"	3234	2050'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. MIRU PU, TOH W/2-1/16" TBG. PMPD 2 SXS HULLS & 20 SXS CMT. DISPLACE TO 2830 W/9 PPG MUD. PMPD 2 SXS HULLS & 20 SXS CMT. DISPLACED TO 2200. PULL FREE POINT ON 4-1/2" CSG. SHOT OFF 4-1/2" CSG @ 2050'. TOH W/4-1/2" CSG. PULL FREEPOINT ON 8-5/8" CSG. SHOOT OFF 8-5/8" CSG @ 630'. CIRC HOLE FULL OF 9 PPG MUD. PMPD 110 SXS. PLG FROM 550-400'. TOH W/8-5/8" CSG. PMPD 25 SXS CMT FROM 40-4'. CUT OFF & CAP 13-3/8" CSG 4' BELOW GL. INSCRIBE CAP RESTORE LOCATION. NOTIFIED KCC REP GARY WINTERS.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT & HORTON PLUGGING, INC. License No. 31151

Address RT. 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE: (405) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, SS.

JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John A. Broman  
JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 23rd day of September, 1997.

Shirley Childers  
Notary Public

My Commission Expires:

