

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
130 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-189-223390000

LEASE NAME SCHMIDT "D"

WELL NUMBER 1

2970 Ft. from S Section Line

1700 Ft. from E Section Line

SEC. 27 TWP. 32S RGE 39 (E) or (W)

COUNTY STEVENS

Date Well Completed 6-15-2000

Plugging Commenced 6-16-2000

Plugging Completed 6-17-2000

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-15-2000 (date)

by MR. RICHARD LACEY (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached?

Producing Formation NONE Depth to Top Bottom T.D. 6302

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	1632'	NONE

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. TIH W/4 1/2" DP TO 3200' & SPOT 100 SKS 60/40 POZMIX, 6%GEL @ 3200', TOH TO 1660' & SPOT 50 SKS, TOH TO 600' & SET 40 SKS, TOH TO 40' & SET 10 SKS FROM 40' TO 0'. SET 10 SKS IN MH & 15 SKS IN RH. CUT OFF 8-5/8" CSG 3' BELOW GI AND CAP, PERMANENTLY INSCRIBE WELL NAME, NUMBER AND DATE PLUGGED ON CAP.

(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION

Name of Plugging Contractor DOWELL-SCHLUMBERGER License No. 116095

Address 204 S. MISSOURI, ULYSSES, KANSAS 67880

JUL 07 2000

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS COUNTY OF SEWARD, ss.
L. MARC HARVEY, DRILLING TECHNICAL ASSISTANT (Employee of Operator) or (Operator) of above-


described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) L. Marc Harvey 6-30-2000
L. MARC HARVEY, DRILLING TECHNICAL ASSISTANT
(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 30th day of June, 2000

Shirley J Childers
Notary Public

My Commission Expires:



Form CP-4
Revised 05-88