

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Morton County, Sec. 1 Twp. 32S Rge. 40 ~~X~~ X (W)

Location as "NE/CNW/SW" or footage from lines C NW SE
Lease Owner Cities Service Oil Company
Lease Name Drew "A" Well No. 2
Office Address Box 1228, Guymon, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed 5-5 1962
Application for plugging filed 8-8 1969
Application for plugging approved 8-11 1969
Plugging commenced 9-25 1969
Plugging completed 10-30 1969
Reason for abandonment of well or producing formation Uneconomical to produce

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 8-12 1969
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. E. Eves, Sublette, Kansas
Producing formation Morrow S-3 Depth to top 5662 Bottom 5744 Total Depth of Well 6040 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Morrow S-3	Gas	5662	5744	8 5/8	1705	None
				4 1/2	5845	2107

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Cement plugs were spotted as follows: Spotted 50 sx. of 50/50 pozmix from 5025' to 5662' in 4 1/2" casing. Mud from 5025' to 850'. Spotted 60 sx. of cement from 682' to 850'. Mud from 45' to 682'. Spotted 15 sx. cement from 4' to 45'. Cut off 8 5/8" casing 4' below ground level and welded on steel cap with well name and date on cap.

RECEIVED
STATE CORPORATION COMMISSION
NOV 3 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Daco Well Service
Address 1700 S. Main, Borger, Texas

STATE OF OKLAHOMA, COUNTY OF TEXAS, ss.
H. E. Massey (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. E. Massey
Dist. Manager, Box 1228, Guymon, Oklahoma
(Address)

SUBSCRIBED AND SWORN to before me this 31st day of October, 1969

My commission expires 7-9-73

Melvin E. Dudley
Notary Public

Drillers Log
Drew "A" #2
Sec. 1-32S-40W
Morton Co., Kansas

Sand & Clay	0 - 685
Red bed, Anhydrite	685 - 895
Red bed, Sand	895 - 1180
Anhydrite, Gyp, Shales	1180 - 1371
Anhydrite, shales	1371 - 1690
Anhydrite	1690 - 1706
Shale	1706 - 1890
Shale & Lime	1890 - 2136
Shale	2136 - 2280
Lime & Shale	2280 - 2595
Lime	2595 - 2712
Lime & Shale	2712 - 2860
Lime	2860 - 3323
Lime & Shale	3323 - 3511
Lime	3511 - 3700
Lime & Shale	3700 - 3808
Lime	3808 - 5083
Lime & Shale	5083 - 5835
Lime	5835 - 5967
Lime & Shale	5967 - 6029
Lime	6029 - 6040
T.D.	6040

RECEIVED
STATE CORPORATION COMMISSION
AUG 11 1969
CONSERVATION DIVISION
Wichita, Kansas