

15-189-00037-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stevens County. Sec. 9 Twp. 32S Rge. 36W (E) (W)
Location as "NE/CNW/SW" or footage from lines C NE SW
Lease Owner Northern Natural Gas Producing Company
Lease Name Stout "A" Well No. 1
Office Address 2223 Dodge Street, Omaha, Nebraska
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 4 19 56
Application for plugging filed July 4 19 56
Application for plugging approved July 4 19 56
Plugging commenced July 4 19 56
Plugging completed July 4 19 56
Reason for abandonment of well or producing formation Oil in commercial quantities not found
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 6302 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13-3/8"	650'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with extra heavy rotary mud from 6302' to 2900'. 165 sacks cement from 2900' to 2500'. Filled hole with extra heavy rotary mud from 2500' to 600'. Set Plug #1 and 40 sacks cement from 600' to 550'. Filled hole with extra heavy rotary mud from 550' to 40'. Set Plug #2 and 35 sacks cement from 40' to 3', with steel plate welded on surface pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Capitt Drilling, Inc.
Address 1005 Central Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF Sedgwick, ss.
L. J. Clampitt (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. CAPITT DRILLING, INC.

(Signature) [Signature]
1005 Central Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of July, 1956

My commission expires September 30, 1959

[Signature]
Notary Public.
COMMISSION

PLUGGING
FILE SEC 9 T 32 R 36W
BOOK PAGE 78 LINE 12

7-12-56
CONSERVATION DIVISION
Wichita, Kansas

ROTARY DRILLING LOG

OPERATOR: Northern Natural Gas Producing Co.
Stout #1 "A"
C NE SW Section 9-32S-36W,
Stevens County, Kansas

CONTRACTOR: Capitt Drilling, Inc.
COMM: 5/28/56
COMP: 7/4/56

Formations:

Shale	170'
Sand Shale	200'
Sand	515'
Red Rock	540'
Red Shale	605'
Red Rock	1135'
Lime Red Rock	1165'
Red Rock Shells	1530'
Sand	1600'
Red Rock & Lime	1728'
Red Rock	1770'
Lime	1805'
Lime Shale	1890'
Anhydrite Lime & Shale	2360'
Lime & Shale	3700'
Lime	3815'
Shale Lime	3865'
Lime	4065'
Lime (dense, cherty)	4100'
Lime w/ shale	4119'
Core #1	4177'
Shale & Lime	4210'
Lime	4832'
Lime & Shale	4960'
Lime	5185'
Lime & Shale	5251'
Lime	5415'
Lime & Shale	5520'
Core #2	5571'
Core #3	5628'
Core #4	5685'
Core #5	5742'
Core #6	5800'
Core #7	5858'
Core #8	5943'
Core #9	5957'
Lime	5988'
Shale & Shells	6070'
Lime	6302'
Rotary Total Depth (D&A)	6302'

Remarks: Set 13-3/8" surface casing
at 650' cemented with 600 sacks Pozmix
with 2% C. C.

We certify the above log is true
and correct to the best of our
knowledge and belief.

CAPITT DRILLING, INC.

R. R. McNicol

R. R. McNicol

RECEIVED
STATE OF KANSAS

JUL 11 1956

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 9 T 32 R 36W
BOOK PAGE 78 LINE 12