

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-189,20,908-0000

LEASE NAME L. L. Barngrover

WELL NUMBER #1

500 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 3 TWP. 32 RGE. 36 (E) or (W)

COUNTY Stevens

Date Well Completed None

Plugging Commenced 6/13/86

Plugging Completed 6/16/86

LEASE OPERATOR Mobil Oil Corporation

ADDRESS P.O. Box 5444, Denver, CO 80217

PHONE# (303) 298-2696 OPERATORS LICENSE NO. 5208

Character of Well Dry

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes if not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top 5897 Bottom 5934 T.D. 6550

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

*CL*

Formation	Content	From	To	Size	Put in	Pulled out
L. Morrow	-0-	0	1834 6543	8 5/8 24# 5 1/2 15.5#	K-55 X K-55 X	None None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plug #1 set Gearhart C.I.B.P. at 5860' w/2 sax cement on plug. Circulate hole 5860' to 5813' with 40 vis. Plug #2 set 3225 to 2970 w/30 sax 60/40 POZ cement. Perforated 4 S.P.F. 1880 to 1878 & set Howco EZSV retainer at 1760' EST circulation + PAMPED 125 sax 60/40 POZ cement between 5 1/2 & 8 5/8 csg. Plug #3. 1100' approx. to 900' w/20 sax 60/40 POZ cmt. Plug #4 40' to 0'. Inside

(If additional description is necessary, use BACK of this form.) csg w/5 sax cement Cut to weld plate to csg. 6' below G.L.

Name of Plugging Contractor Halliburton Services Co. License No. \_\_\_\_\_

Address Hwy 54 West, Liberal, KS 67901 Phone #316) 624-3879

STATE OF Colorado COUNTY OF Denver, ss.

A. Williams (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) J. E. Dawson

(Address) P.O. Box 5444, Denver, CO 80217

SUBSCRIBED AND SWORN TO before me this 30<sup>th</sup> day of July, 19 86

Deborah A. Cavette  
Notary Public

My Commission Expires: MY COMMISSION EXPIRES 7/2/90

AUG 4 1986 8-4-86

Form CP-4  
Revised 08-84