

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

0000  
API NUMBER 15-189-20,303-

LEASE NAME Larrabee

WELL NUMBER #4

SPOT LOCATION 660 FSL 660 FEL

SEC. 13 TWP. 32 RGE. 35 (N) or (W)

COUNTY Stevens

Date Well Completed 4-5-76

Plugging Commenced 1-21-1988

Plugging Completed 1-25-1988

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

Claassen  
LEASE OPERATOR Claassen Exploration  
ADDRESS 427 S. Boston, Suite 1901, Tulsa OK 74103

PHONE # (918) 599-0409 OPERATORS LICENSE NO. 04951

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing formation Chester  
St. Louis Depth to top 6110' bottom 6120' T.D. 6199'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface				8 5/8"	1715'	0'
Production				5 1/2"	6197'	2750'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pump 2 sks. hulls and 25 sks. cement to 5900', pump 25 sks. @ 2750' - Mud 2750' to 1780' - Pump 50 sks. 1780' to 1680' - Mud 1680' to 710' - Pump 25 sks. 710' to 635' - Mud 635' to 40' - Put bridge and 10 sks. 40' to 0' - Cut off 8 5/8", 3' below ground level and cap

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6479  
Address Box F, Sublette, Ks. 67877

STATE OF KANSAS COUNTY OF HASKELL, ss.

I, Edgar J. Eves

(employee of operator) or (operator) of above-described well, being duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

2-16-88

(Signature) Edgar J. Eves  
(Address) Box F, Sublette, Ks. 67877

SUBSCRIBED AND SWORN TO before me this 29 day of Jan., 1988

My Commission expires: 12-6-88

Sondra L Eves  
Notary Public

