

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-189-21,041- <sup>0001</sup>

LEASE NAME Larrabee

WELL NUMBER 6

SPOT LOCATION 4620' ESL & 4180' FEL

SEC. 13 TWP. 32 RGE. 35 ~~XXX~~ or (W)

COUNTY Stevens

Date Well Completed May 1987

Plugging Commenced 3-9-1989

Plugging Completed 3-13-89

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Claassen Exploration Co.

ADDRESS 427 S. Boston, Su. 1901, Tulsa, OK 74103

PHONE # 918, 599 - 0409 OPERATORS LICENSE NO. 04951

Character of Well gas  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes if not, is well log attached? \_\_\_\_\_

Producing formation Council Grove Depth to top 2956 bottom 2996 T.D. 6200'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface				8 5/8"	1715	0'
Production				5 1/2"	6197'	2021

4-24-89  
RECEIVED  
STATE CORPORATION COMMISSION  
APR 24 1989  
CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pump 2 sks. hulls and 25 sks. cement to 2750 - pressured to 700 lbs. - Pump 50 sks. cement 1650' to 1550'  
Mud 1550' to 700' - pump 40 sks. cement 700' to 600'  
Mud 700' to 40' - put bridge and 10 sks. cement 40' to 3'  
Cut off 8 5/8", 3' below ground level and cap

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor MIDWEST CASING PULLING SERVICE License No. 6497  
Address Box F, Sublette, Ks. 67877

STATE OF KANSAS COUNTY OF HASKELL, ss.

I, Edgar J. Eves (XXXXXXXXXXXXXXXXXXXX) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Edgar J. Eves  
(Address) Box F, Sublette, Ks. 67877

SUBSCRIBED AND SWORN TO before me this 15 day of March, 19 89

Sondra L. Eves  
Notary Public

My Commission expires: 12-6-92