

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-189-21,363-0000

LEASE NAME Fern Sessler

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER 2-21

2310 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 21 TWP. 32 RGE. 35  or  W

LEASE OPERATOR McCoy Petroleum Corporation

ADDRESS 110 S. Main, Suite 500

COUNTY Stevens

PHONE# (316) 265-9697 OPERATORS LICENSE NO. 5003

Date Well Completed 8-2-89

Character of Well D & A

Plugging Commenced 8-1-89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-2-89

The plugging proposal was approved on 8-1-89 (date)

by \_\_\_\_\_ (KCC District Agent's Name).

is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

T.D. 6470'  
 RECEIVED  
 STATE CORPORATION COMMISSION  
 8-7-89  
 AUG - 7 1989

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	1784	8-5/8"	1784'	None

CONSERVATION DIVISION  
 Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Plug using Halliburton Pump Truck with 60-40 Pozmix, 6% gel. Set 1st Plug @ 3200' w/100 sx. 2nd plug @ 1810' w/50 sx., 3rd plug @ 800' w/40 sx., 4th plug @ 40' w/10 sx. 15 sacks in ratehole and 10 sacks in mousehole. Plugging Complete @ 5:00 A.M. 8-2-89.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sweetman Drilling, Inc. License No. 5658

Address 110 S. Main, Suite 500


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation

STATE OF Kansas COUNTY OF Sedgwick, ss.

McCoy Petroleum Corporation (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 110 S. Main, Suite 500  
 Wichita, Kansas 67202



SUBSCRIBED AND SWORN TO before me this 4th day of August, 19 89

[Signature]  
 Notary Public

My Commission Expires: 1-8-92